

## Hurricane Hardening Research

Presentation to the Louisiana Public Service Commission

May 4, 2007


Mark A. Jamison, PURC Director





### Overview

- Background on PURC
- Impetus for Hurricane Hardening Research Coordination
- Research Projects



## PURC Background

- Founded in 1972
- Located in the Economics Department, Warrington College of Business Administration
- Purpose: Enhance executives', regulators', academics', and students' knowledge of issues confronting public utilities and regulatory agencies
- Support: Utilities and FPSC, programs, and research

## PURC Research, 2002-2006

	Number			
Туре	Intl.	Domestic	Either	Total
Applied Journals	9	6	8	23
Academic Journals	5	10	19	34
Books			1	1
Book Chapters	2	2	13	17
Working Papers	9	20	20	49
Case Studies	2	2		4





# PURC Recent and Ongoing Research Topics

#### General

- Service Quality
- Leadership
- Body of Knowledge
- Regulatory Associations
- Stability of Regulatory Institutions
- Regulatory Risk

#### **Energy**


- Distributed Generation
- Pricing and Rate Design
- NOx, SO2, and Climate Change Policy
- Fuel Diversity and Policy Uncertainty

#### <u>Telecoms</u>


- Telecom Competition
- Ownership of Utility Services
- Universal Service Programs
- Net Neutrality


#### Water

Benchmarking Water
 Utilities in Central America



# Body of Knowledge on Utility Regulation visit www.regulationbodyofknowledge.org





## **PURC Programs**

#### **Domestic**

- PURC Annual Conference
- Leadership workshops
- Roundtables
- Bar Association Conf.

#### <u>International</u>

- PURC/World Bank International Training Program
  - > 1700 people; 131 countries
- PURC/OOCUR Advanced Training Program

#### International (Cont.)

- Standing Cooperative Programs – University of Cape Town, IIS-Zambia
- Recent Custom Training Programs and Other Outreach
  - Telecoms Thailand,
     Trinidad & Tobago,
     Nigeria, Uganda
  - Energy Cambodia,
     Peru, South Africa, Brazil,
     Mexico, Namibia
  - Water Uganda, China




# Impetus for Hurricane Hardening Research





## 2004 Hurricane Season







# 45 Days, 4 Hurricanes... 23 Days of Restoration Activity

	Charley	Frances	lvan	Jeanne
Date of landfall	A ug 13	Sept 5	Sept16	Sept 26
C ategory at peak	C at4	C at2	C at3	C at3
Peaknumberof customersout	502,000	832,898	10,000	722,000
Substationsout	83	105	3	86
D aysofstorm restoration	10Days	7 Days	1Day	5Days






## 2004 System Impact, TECO

	<u>Charley</u>	<u>Frances</u>	<u>Jeanne</u>
<u>Distribution</u>			
Circuits Out	68	223	252
Lights Out	353	2519	639
Wire Down (spans)	2,540	5,780	6,600
<u>Transmission</u>			
Circuits Out	17	21	42
Wire Down (spans)	74	34	151
<u>Substations</u>			
Distribution Out	23	46	70
Transmission Out	17	21	42



# Storm Season 2004-2005, FPL 7 Storms / 15 Months

#### 2004 Season



Event	Affected Customers	Days to Restore 100%
Charley	874,000	13
Frances	2,786,300	12
Jeanne	1,737,400	8
Dennis	508,800	3
Katrina	1,453,000	8
Rita	140,000	2
Wilma	3,241,437	18

Hurricane force winds



**Tropical storm force winds** 



14

Source: FPL


# FPL 2005 - Distribution and Transmission Repair

### Distribution

- 12,632 poles (FPL & non-FPL)
- 930 miles of OH conductor
- 570 miles of OH service conductor
- 1.1 million OH splices
- 30 miles of UG cable
- 100 miles of UG service cable

### Transmission / Substation

- 100 structures
- 7 miles of conductor
- 1 substation transformers
- 7 regulators
- 16 breakers










## FPSC Response


- Workshops with utilities, consultants, and academics on how best to prepare Florida's electric infrastructure for hurricanes
- New standards
- Ongoing monitoring and reporting

http://www.psc.state.fl.us/utilities/electricgas/eiproject/




# FPSC 9-Point Preparedness Plans

- 3-year vegetation management cycles
- Trans. and distribution geographic info system
- Upgrade wooden structures
- Data gathering, retention, and forensic analysis
- Audit joint-use pole attachment agreements
- 6-year transmission inspection program
- Track outage data for overhead vs. underground
- More utility coordination with local government
- Collaborative research coordination




## Why Research Coordination?

- Concerned that utilities were generally unaware of each other's research efforts
- Desire to increase focus on hardening research
- Interest in making research results generally available




## Research Approach





### Research Coordination Effort

- Sponsored by all electric utilities in the state and governed by Steering Committee
  - IOUs: FPL, Progress, Gulf Power, TECO, FPU
  - Municipal Association
  - Coop Association
  - Lee County Electric Cooperative
- PURC coordination
  - Manage process; review research plans and products for academic standards



## Workshop, June 9, 2006


- Utility managers
  - Review of hurricane experiences and key knowledge gaps
- Researchers
  - Research experiences and capabilities
    - UF, FSU, USF, Texas A&M, Cornell, Davies Consulting, Applied Research Associates



## Workshop Conclusions

#### Practical research needed on


- Wind measurement and testing
- Improved materials
- Forensic analysis
- Cost-effectiveness of approaches
  - Overhead vs. underground
  - Vegetation management
  - Wind standards
- Joint use loads



## Research Agenda

- Economics of Undergrounding Existing Overhead Facilities
  - Addresses cost-effectiveness issue
- Granular Wind Analysis
  - Addresses wind measurement and testing, forensic analysis, and standards
- Vegetation Management best practices

http://bear.cba.ufl.edu/centers/purc/energy/hurricane.htm




## Undergrounding Research

- Launched in Fall 2006
- Consultant: InfraSource (Richard Brown)
- Phases
  - I Meta-analysis of existing literature to see what is already known (completed)
  - II Case studies on what might be unique about Florida (underway)
  - III Computer model to project costs/benefits of specific undergrounding requests (starts in June)

#### **Undergrounding and Storm Surge**

Pensacola Beach: Single Phase cabinet washed off pad and cables pulled out of terminations.






Meta-Analysis

- Examined 61 documents
  - Consultant Reports
  - State Regulatory Reports
  - Municipal Reports
  - International Reports
  - System Reliability Modeling
  - Failure Rate Modeling
  - Property Value
- Primary Issues
  - Cost
  - Benefits
  - Disadvantages
  - Funding









# Meta-Analysis Executive Summary

#### **Existing Studies show:**

- Undergrounding has both benefits and disadvantages
- Quantifiable benefits cannot justify undergrounding
- Undergrounding is expensive
  - About \$1 million per mile (initial cost)
  - Customer service work costs extra
  - Cost can vary widely
  - Broad implementation requires rates to about double

- Undergrounding requires additional costs
  - Third-party attachments (add 25% to initial cost)
  - Customer equipment (\$1,500 to \$7,000 per customer)
  - Funding additional costs is a critical element
- Funding in general is a critical element



## Other Findings

- No state requires undergrounding of existing facilities
- Ex post analyses on actual UG projects have not been done
- Few studies address negative impacts
- Few studies consider strengthening existing overhead systems
- Storm reliability models are almost non-existent
- Equipment failure rates as a function of hurricane strength are almost non-existent
- Existing research on mitigating the impacts of major storms on electric distribution is not sufficient for use in a detailed study



## Florida 2005 FPSC Study

- Conversion Cost Estimates (IOUs)
  - Residential subdivision: \$2,475 per customer affected
  - Residential feeders: \$11,288 per customer affected
  - Mainline urban commercial: \$36,737 per customer affected

- Costs do not include
  - Customer service equipment
  - Third-party attachments
- Rate impact
  - 81% increase if spread over all customers
  - 141% increase if spread over residential customers only



#### Davis Island

- \$3,200 per customer for a 3000 customer project
- Fort Pierce
  - Broad conversion is not iustifiable
  - Overhead hardening may be preferable
- Jacksonville
  - \$3,000 to \$7,000 per customer
- Tallahassee
  - High environmental impact in sensitive areas





"Leadership in Infrastructure Policy"

### Florida Studies



#### Palm Beach

Total UG cost would be \$60 million

#### **MUUC** Report


Difference of UG vs. hardened OH is \$835,000 per mile



30

Source: InfraSource

www.purc.ufl.edu




# Conclusions Regarding Insights for Modeling

#### **Assessment of Proposed Projects**

- Construction cost models are adequate
- Maintenance cost models are adequate
- Storm reliability models are inadequate
  - Equipment hurricane failure rates are not well known
  - The effects of mitigation tactics are not well known
  - Detailed hurricane simulation planning models do not exist

Source: InfraSource



### **Timeline**

- Case studies
  - August 6, 2007 Final Report
- Computer model development
  - October 1, 2007 Final Report on methodology
  - March 30, 2008 Model and testing completed





### Wind Research

- Coordinated effort of UF Civil Engineering, WeatherFlow, Utility Sponsors, and PURC
- Purpose: Measure hurricane winds at granular level and map to infrastructure damage
  - Forensic Analysis
  - Test using hurricane simulator




# FCMP TOWERS





## Motivation for Portable Towers

- Winds overland differ from winds over the ocean (over water is the basis for SSscale)
- Mean speed is lower and turbulent gusts are more severe in winds overland
- Can't fix a problem without understanding the cause
- Evaluation of infrastructure vulnerability (and hardening solutions) must start by filling this knowledge gap via direct wind measurements



### Questions to Address

- How do we know what winds have really caused damage?
- How do we know what winds the infrastructure has actually withstood?

## Existing Portable Weather Stations










- Stiff 10-m Steel Lattice Tower
- Remain stable in 200 mph winds
- Self-powered



- Instruments collect wind speed and environmental data
- Quick setup to hasten retreat from approaching storm

Source: Gurley




### New Fixed Weather Stations

Developed, placed, and managed by

WeatherFlow http://www.weatherflow.com/index.php

- Tested and upgraded by UF Civil Engineering, Kurt Gurley
- Currently 12 stations
  - Anticipating 40






### Wind Station Uses

 Monitor wind, barometric pressure, temperature 24/7/365

Data to sponsors, UF, PURC,





NOAA on proprietary basis

Forensic analysis and NOAA maps



# NOAA Hurricane Research Division Maximum Sustained Wind Swath





# Capacity testing without a hurricane

 Housing infrastructure can be tested under applied controlled loads to evaluate failure strength

 Same concept can be applied to power distribution infrastructure

# FIELD TESTING – ROOF CONNECTIONS



- Test as-build capacity
- Install retrofit
- Test retrofit capacity
- Relate forces to winds
- Evaluate effectiveness

Source: Gurley

www.purc.ufl.edu

# FIELD TESTING - SHEATHING CAPACITY



- Cut out sheathing and trusses
- Apply suction load until failure
- As-nailed
- Re-nailed

Source: Gurley

www.purc.ufl.edu



## Vegetation Management

- Best Practices workshop, March 5-6, 2007
  - Report available online
  - http://bear.cba.ufl.edu/centers/purc/energy/hurricane.htm
  - Selected key conclusions
    - Laws needed for utility access
    - Better communications are needed
    - Not directly relevant to hurricanes



### Conclusions

- Collaborative research has been a success thus far
  - Good projects initiated and sound results
  - Utilities working together and supportive of effort is critical
  - Many of the research questions are applied, so academic research is needed only in selected areas